



Addendum-II

To

REQUEST FOR PROPOSALS (RFP)

for

**Electrical, Mechanical and Civil Works Maintenance Services in Peshawar
BRT System (Miscellaneous Services)**

Tender No. TPC/Operations/Services/PQ/MS/2022-23/003

Note: This addendum shall supersede and become integral part of the original document.

Date: 13-09-2022

Electrical, Mechanical and Civil Works Maintenance Services in Peshawar BRT System (Miscellaneous Services)

1.9	Supply, pulling/laying in conduit and termination in DB/Equipment of 4 core 35 Sq.mm Aluminium cable at various location along the corridor. Any other works required for intended purposes cleaning of JB/ clearing Conduit and restoration of the system as per original shall also be included in the scope.	Meter	2000 1000		
1.10	Supply and laying of 1st class brick work in sand cement mortar of 1:4 at different locations along the BRT Corridor as directed by TPC.	Cubic meter	6		
1.11	Arrangement of Trolley/Dumping vehicle for collection and Transportation of various waste items form different location of corridor to KPUMA.	Per Trip	10		
1.12	Repair and fixing with grouting material of existing railing on underpasses with M16, 4inch long stainless-steel nut and bolt including painting/ welding etc. The job will also include placing /re-fixing of tiles on the surfaces of retaining walls with railing along the BRT corridor complete in all respect or as per direction of TPC.	Job	8		
Item No	Item Description	Unit	Quantity	Rate per Unit (PKR)	Total Amount (PKR)
2	BRT Stations and allied Infrastructure repair and maintenance Works- The Installation of routes Sign boards, 2 core 16mm.sq Aluminium cable, Energy meter, tented stickers, 15A Socket and installation of SCADA Panels.				
2.1	Supply and fixing of acrylic board containing 3 removeable boards of A4 size along with farm having printed instruction/ images on both sides at	Nos	100		